

Lab 2 - Objectives

How to verify

- Connectivity is always tested from the PC/server in each network
- Internet = 8.8.8.8

Inside net

- Can ping to all devices & internet except for the ones in the DMZ net, these should only be reachable with TCP
- TCP connectivity test: ping -3

Outside net

- Can ping the internet and can reach the devices in the DMZ only via UDP
- UDP connectivity test: ping -2

DMZ

- Devices are only allowed connectivity with internet and outside net

HSRP

- Virtual IP address should failover to R2 when R1's interface in the inside net goes down
- When this interface comes back up the Virtual IP should go back to R1

NAT Overload

- NAT Overload needs to be functional for all subnets, verify by pinging 8.8.8.8 from the virtual PC's/server in each network

